

## **1.0 GENERAL**

- .1 The Contractor is responsible to have all underground utilities located. Contact the utility companies a minimum of 48 hours in advance.
- .2 The Project Manager will mark the alignment for the installation of the uniform fence. The Contractor shall contact the Project Manager, to request the marking of the alignment, 48 hours prior to calling for locates.
- .3 Uniform fence to be installed on private property side of the property line.

## **2.0 MATERIALS**

### **2.1 LUMBER**

- .1 1.8 m (5.9 ft) polymer coated lumber. "Woodguard" is registered trademark.
- .2 Colour: white
- .3 2.7 m (9 ft) posts polymer coated lumber. 2.4 m (8 ft) posts concreted in is an acceptable alternative.
- .4 Randesign (924B South Railway Medicine Hat, Alberta Phone: (403) 580-4438) is western Canada distributor.

## **3.0 INSTALLATION**

- .1 Fence boards installed facing the City roadway, with approximately 50 mm (2 inch) spacing between boards.
- .2 Posts installed on 2.4 m (8 ft) centre.
- .3 Posts to be packed with native soil.
- .4 Fence boards, rails and posts to be installed according to manufacturers specifications.
- .5 The contractor shall measure 9.0 m (29.5 ft) from the back of curb face, in both directions from the corner of the intersection. These two points shall be connected to form a triangle and any fence that is within this triangle shall be stepped down to 0.8 m (2.5 ft) height at street intersections. The contractor shall confirm with the Project Manager the amount of fence to be stepped down.

**4.0 SITE CLEAN UP**

- .1 The Contractor shall take every precaution not to damage, injure or mark existing surfaces, structures or landscaping on the City owned property or adjacent private properties.
- .2 Any damage that may be caused by the Contractor, his employees or equipment or subcontractors, shall be restored to pre-construction condition at the Contractor's expense and to the satisfaction of the Project Manager.

**5.0 INSPECTION**

- .1 Upon completion of installation, the contractor shall arrange for inspection.

**END OF SECTION**