

1.0 GENERAL

1.1 INSPECTION

- .1 The Project Manager will inspect the work upon notification by the Contractor, at the following stages of the work:
 - .1 after subgrading is complete, finished grades are established and results of soil tests have been provided to the Contractor and topsoil composition has been approved by the Project Manager
 - .2 after placement of topsoil, but before seeding or sodding
 - .3 after irrigation lines are laid and tested, but before trenches are backfilled and compacted
 - .4 during start-up of the irrigation system
 - .5 within 10 working days after the receipt of an application from the Contractor for substantial performance of the work
 - .6 within 10 working days after the receipt of an application from the Contractor for Total Performance of the work
 - .7 within 10 working days prior to the expiration of the guarantee period
- .2 The Contractor shall advise the Project Manager at each stage when the work is ready for inspection and the Project Manager shall, within one (1) working day of the receipt of such notification, provide an inspector who shall inspect the work in progress to ensure compliance with the approved plans.
- .3 The Project Manager shall provide the Contractor with a completed inspection report within three (3) working days after each of the above inspection phases.
- .4 The Project Manager will conduct inspections as outlined in these specifications and any work that does not conform to the specifications shall not be approved until the work conforms to the specifications.
- .5 The Contractor shall not proceed with the next step in the sequence of work until the Project Manager has provided the Contractor with written authorization to proceed.
- .6 The inspection of the work by the Project Manager shall in no way relieve the Contractor of his duty to adhere to the specifications which are part of the Contract.

END OF SECTION