

1.0 GENERAL

1.1 SITE CLEARING

- .1 All trees presently growing on the site which are to remain shall be protected to avoid any damage to them during construction operations. The Contractor shall not excavate or use heavy equipment in proximity to the tree and shall stay a minimum of 5 metres away from the trunk, or outside the drip line, whichever is the larger value.
- .2 The Contractor will be charged a penalty for any damage to existing trees based on the value of the tree, as established by the International Society for Arboriculture Value Guide.
- .3 Dead trees shall be cut and stumps removed to a minimum depth of 600 mm (24 inches) below proposed finished grades.
- .4 The burying of any materials on the site shall not be permitted.
- .5 Burning of debris on the site shall not be permitted.

END OF SECTION